



NOTES

- (1) Enclosure foundation may be incorporated with padmount transformer foundation.
- (2) Precast concrete pads available through vendor: 4500 psi concrete, weighing 1497 lbs. Catalog ID 0100-006043.
- (3) Existing grade and back fill under concrete pad shall be compacted to 95% in accordance with ASTM D1557.
- (4) Cast out 12" x 18" sections. After conduits are in place, fill in remaining area with Quikrete to rodent proof the equipment. Minimum rodent proof thickness is 2".
- (5) 4" Rigid galvanized, PVC or IMC duct with bushing.

REFERENCES

- (1) See DS-7-16.10 Guard Post
- (2) See MS-3-17.0 7200/12470V CT and PT Meter Enclosure
- (3) See MS-7-2.0 Working Space Required for Meter Enclosure
- (4) See MS-3-21.0 7200/12470V CT and PT Enclosure Pad

7200/12470V CT and PT Meter Enclosure Precast Pad

DS-7-17.2